

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19123-00-01
Spot: SENWNENE Sec/Twnshp/Rge: 7-12S-17W
4836 feet from S Section Line, 789 feet from E Section Line
Lease Name: HERMAN Well #: 3
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3729		100 SX
SURF	8.625	203		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2014 8:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORP Phone: (785) 623-2084

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
Squeezed at 1024' w/200 sx cement Jan 1977.
Well was previously plugged. Casing cut off at 2954'.
ARB: 3652' - 3730'. PBTD-3709'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2014 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling ran in hole with tubing to 2900'. Quality mixed and pumped 13 sx gel followed by 50 sx cement w/200 # hulls mixed in. Pulled tubing to 1850' and pumped 130 sx cement w/300 # hulls to circulate cement to surface. Pulled tubing. Rigged to 5 1/2" casing with a swedge and pumped 15 sx cement to pressure with 200 psi and 200 psi shut in pressure. Rigged to 8 5/8" casing and pumped 30 sx cement to pressure with 150 psi and 150 psi shut in pressure.

GPS: 39.02945 -099.24432
4837' FSL 749' FEL
SE NW NE NE

Perfs:

Top	Bot	Thru	Comments
3696	3700		
3680	3684		

KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING TICKET # 7187


APR 07 2014

Plugged through: TBG

RECEIVED

District: 04

Signed



(TECHNICIAN)

CM

MAR 28 2014