

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24985-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 23-20S-13W
470 feet from N Section Line, 2030 feet from E Section Line
Lease Name: LONNON B Well #: 1
County: BARTON Total Vertical Depth: 3599 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3593 | | 150 SX |
| SURF | 8.625 | 320 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed
Plugging
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement, 16 sx gel and 300 # hulls.

Plugging Proposal Received By: BRUCE RODIE
Date/Time Plugging Completed: 03/25/2014 11:00 AM

Witness Type: COMPLETE (100%)
KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 705' and 300'.
Ran tubing to 3500' and pumped 16 sx gel followed by 60 sx cement w/100 # hulls. Pulled tubing to 1294' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 694' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 300'. Circulated cement to surface on casing w/95 sx cement. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe with 30 sx cement.

GPS: 38.30315 -098.72651

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3390 | 3392 | | |

KCC WICHITA

Remarks: ALLIED CEMENT COMPANY TICKET # 62694

APR 07 2014
RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

4/17/14

CM

MAR 27 2014

Form CP-2/3