

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22209-00-00
Spot: S2NWNWSW Sec/Twnshp/Rge: 22-17S-30W
2280 feet from S Section Line, 330 feet from W Section Line
Lease Name: CRAMER Well #: 1-22
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2248		CEMENTED WITH 200 SX CMT. 20 SX CMT CIRCULATED TO PIT.
PROD	4.5	4611	0	WITH 225 SX CMT
SURF	8.625	261		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 12:15 PM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: SAND PERFS TO 4200' WITH 2 SX CMT. RTIH TO 2220' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 2:15 PM KCC Agent: DANIEL SELLERS

Actual Plugging Report:

SANDED PERFS TO 4160' WITH 2 SX CMT. RTIH TO 2220' & CIRCULATE CMT TO 0' WITH 140 SX CMT. CHECK BACKSIDE WITH 200#. TOOK 5 SX CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4527	4529		
4519	4521		
4437	4440		
4361	4363		
4324	4326		
4280	4283		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

APR 09 2014

RECEIVED

District: 01

RECEIVED

APR - 3 2014

KCC DODGE CITY

Signed

Daniel Sellers
4/17/14
(TECHNICIAN)

any