

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21852-00-00
Spot: SESWNW Sec/Twnshp/Rge: 32-13S-14W
2310 feet from N Section Line, 990 feet from W Section Line
Lease Name: BOXBERGER B Well #: 2
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 33830
Op Name: HEWITT ENERGY GROUP, INC.
Address: 175 S. MAIN ST., STE 900
SALT LAKE CITY, UT 84111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3355		
SURF	8.625	505		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2014 12:00 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: HEWITT ENERGY GROUP Phone: (620) 786-7063

Proposed
Plugging
Method:

Ordered 275 sx 60/40 pozmix 4% gel cement w/300 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2014 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 1498'. Hit metal and hung up. Pulled tubing to 1467' and pumped 100 sx cement. Circulated cement out back side. POOH. Hooked to casing and pumped 135 sx cement. Cement circulated out braden head. Shut in braden head and pumped cement until 300 psi was achieved. Shut in.

GPS: 38.87895 -098.90634

Remarks: QUALITY CEMENTING TICKET # 7136

Plugged through: TBG

KCC WICHITA
APR 14 2014
RECEIVED

District: 04

Signed

Ray A. Dinkel
4/17/14

(TECHNICIAN)

CM

APR 03 2014