

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01743-00-00  
Spot: SWSNW Sec/Twnshp/Rge: 34-17S-8W  
2972 feet from S Section Line, 3674 feet from E Section Line  
Lease Name: ROLFS J F Well #: 5  
County: ELLSWORTH Total Vertical Depth: 3230 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	3207		
PROD	7	3201		300 SX
SURF	10.75	193		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2014 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-4621

Proposed Plugging Method: PER KCC RULES & REGS. CP 1 INDICATES CASING LEAK.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/31/2014 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1100', 800', AND 300'. RUN TUBING TO 3200' AND PUMP 50 SX'S COMMON CEMENT FOLLOWED WITH COTTON HULLS. PULL TUBING TO 1100' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC, LET SET FOR 2 HOURS. TAG @ 850'. PULL TUBING TO 800' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC, PULL TUBING TO 300' AND CIRCULATE 110 SX'S CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF WITH 10 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3201	3230	OH	

KCC WICHITA  
APR 10 2014  
RECEIVED

Remarks: PERF TECH TICKET #11611. QUALITY CEMENT TICKET #497.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
4/17/14 (TECHNICIAN)

1/8