

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00682-00-00
Spot: NWNE Sec/Twnshp/Rge: 31-16S-25W
4659 feet from S Section Line, 1959 feet from E Section Line
Lease Name: LEWIS WILDGEN Well #: 3W
County: NESS Total Vertical Depth: 4518 feet

Operator License No.: 34532
Op Name: TRINITY BAY OIL & GAS INC.
Address: 5219 CITY BANK PKWY, STE 210
LUBBOCK, TX 79407

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4345		WITH 2 SX CMT
PROD	5.5	4498	0	WITH 150 SX CMT
SURF	8.625	216		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2014 8:30 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: MATT CRAIN Company: TRINITY BAY OIL & GAS Phone: (785) 731-5027

Proposed Plugging Method: SET CIBP @ 4340' WITH 2 SX CMT. LOAD HOLE & RUN CASING BOND LOG TO DETERMINE PLUG PROCEDURE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 03/27/2014 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4345' WITH 2 SX CMT. LOADED HOLE AND RAN A CASING BOND LOG. LOG INDICATED THE 5 1/2" CASING IS CEMENTED IN FROM 1970' TO 340'. RAN TBG TO 1976' & CIRCULATED CMT TO SURFACE WITH 250 SX CMT. PULLED TBG OUT OF HOLE. TOPPED OFF 5 1/2" WITH 25 SX CMT. PUMPED 150 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 250 PSIG. SHUT IN AT 100 PSIG.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA
APR 07 2014
RECEIVED

District: 01

Signed Richard W. Lacey
4/08/14 (TECHNICIAN)

RECEIVED
APR - 3 2014
KCC DODGE CITY

RAY