

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-109-20059-00-00
Spot: NESE Sec/Twnshp/Rge: 13-11S-33W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: COOK WATERFLOOD UNIT Well #: 12X
County: LOGAN Total Vertical Depth: 4639 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 4352 | | 150 SX |
| SURF | 8.625 | 259 | | 200 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/25/2014 12:00 PM

Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: 8 5/8" surface casing set at 259' w/200 sx cement. 4 1/2" production casing set at 4352' w/150. TOC at 3677'. TD at 4639'. Perforations: 4271' - 4274', 4250' - 4252' and 4220' - 4222'. Well formerly known as Kruce 'C' # 1.
Ordered 450 sx 60/40 pozmix 4% gel cement w/750 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2014 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 2615' and 1650'.
Ran tubing to 4198' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2799' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1403' and pumped 110 sx cement w/250 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 200 psi.

GPS: 39.09513N -100.92599W

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 44658

Plugged through: TBG

KCC WICHITA

APR 07 2014

RECEIVED

District: 04

Signed Darrel Dipman
4/10/14 (TECHNICIAN)

CM

WAR 27 2014