

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23384-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 33-14S-15W  
1420 feet from N Section Line, 1170 feet from E Section Line  
Lease Name: BAXTER TRUAN UNIT Well #: 1  
County: RUSSELL Total Vertical Depth: 3450 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3439		135 SX
SURF	8.625	435		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/25/2014 8:30 AM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK OIL & OPERATING, LLC  
Proposal Rcvd. from: DAVE FUNK Company: POG Phone: (785) 324-0643

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 5 sx gel and 400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/25/2014 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/24/2014- Perforated at 1550' and pumped 80 BBLS of water down casing on a strong vacuum.  
03/25/2014- Hooked to casing and pumped 75 sx cement w/150 # hulls followed by 5 sx gel. Topped off w/190 sx cement w/250 # hulls. Shut down on vacuum shut in.  
03/26/2014- Ran wire line and tagged top of cement at 134'. Will top off at a later date.  
GPS: 38.79427 -098.98891

Perfs:

Top	Bot	Thru	Comments
3131	3392		

Remarks: QUALITY CEMENTING TICKET # 491

Plugged through: CSG

District: 04

Signed Ray Dinkel  
4/17/14 (TECHNICIAN)

CM

APR 03 2014