

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22747-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 34-14S-15W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: BOXBERGER Well #: 2  
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 6627  
Op Name: PROSPECT OIL & GAS CORP  
Address: PO BOX 837  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3344		160 SX
SURF	8.625	438		210 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2014 8:30 AM  
Plug Co. License No.: 34272 Plug Co. Name: OUTLAW WELL SERVICE LLC  
Proposal Rcvd. from: BRAD HUTCHINSON Company: P.O.G Phone: (785) 483-6266

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/26/2014 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 853' and 400'. Could only get to 890' drilling on iron.  
Ran tubing to 886' and pumped 235 sx cement w/200 # hulls mixed in the last of the cement.  
Cement circulated out both back side and braden head. POOH. Hooked to casing and pumped  
30 sx cement. Circulated out braden head. Shut in and pumped cement to achieve pressure.

GPS: 38.78459 -098.97922

Perfs:

Top	Bot	Thru	Comments
3266	3267		
3156	3157		
3110	3114		

KCC WICHITA

Remarks: QUALITY CEMENTING TICKET # 7096

APR 14 2014

Plugged through: TBG

RECEIVED

District: 04

Signed

*Ray Dinkel*  
4/17/14

(TECHNICIAN)

CM

APR 03 2014