

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR TXO Production Corp. API NO. 15,007-21,152-0000  
 ADDRESS 200 W. Douglas, Suite 300 COUNTY Barber  
Wichita, KS 67202 FIELD Aetna  
 \*\*CONTACT PERSON Harold R. Trapp LEASE Z-Bar Cattle Co.  
 PHONE 265-9441

PURCHASER Delhi WELL NO. Z-Bar Cattle Co. "A" #1  
 ADDRESS 2150 Fidelity Union Tower WELL LOCATION \_\_\_\_\_  
Dallas, TX 75201 330 Ft. from North Line and  
 2100 Ft. from West Line of  
 the 4 SEC. 35S TWP. 15W RGE.

DRILLING CONTRACTOR Freeman, Rig #1  
 ADDRESS 251 N. Water  
Wichita, KS 67202

PLUGGING CONTRACTOR N/A  
 ADDRESS N/A

TOTAL DEPTH 5010 PBTD 4999  
 SPUD DATE 4-18-81 DATE COMPLETED 5-26-81  
 ELEV: GR 1631 DF KB 1643



WELL PLAT  
 (XXXXXX)  
 or (Full)  
 Section -  
 Please  
 indicate.

KCC ✓  
 KGS ✓  
 PLUL ✓

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS  
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	12 1/4"	16"		60'			
Surface		8-5/8"	24#	430'		300	1/2 lite & 1/2
Production		4-1/2"	10.5#	5009'		200	Class H common

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF (2 h.)	Miss.	4956-66'
TUBING RECORD					
Size	Setting depth	Packer set at			
2-3/8"	4930				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
Acidized w/1500 gals 15% DeMud acid	4956-66'
Frac w/170 sxs 16-30# sand + 135 sxs 10-20# sand in 70-qual.	
N2 foam	

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 17 1981  
 11-17-81  
 CONSERVATION DIVISION  
 Wichita, Kansas

TEST DATE: \_\_\_\_\_ PRODUCTION FORMATION: Miss.  
 Date of first production 5-26-81 Producing method flowing A.P.I. Gravity N/A  
 RATE OF PRODUCTION PER 24 HOURS Oil 170 MCFD Gas 170 MCFD Water 12 BF. Gas-oil ratio N/A  
 Disposition of gas (vented, used on lease or sold) Sold Producing interval (s) 4956-66

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

FIELD: Aetna

Name of lowest fresh water producing stratum Unknown Depth N/A  
 Estimated height of cement behind pipe Circulated to Surface

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOG TOPS</u>				
Herington	2192	-549		
Towanda	2335	-692		
Florence	2426	-783		
Foraker	2920	-1277		
Indian Cave ss	3094	-1451		
Wabaunsee	3128	-1485		
Howard	3394	-1751		
Topeka	3460	-1817		
Heebner	4058	-2415		
Up. Douglas	4107	-2464		
Lansing	4254	-2611		
Lansing C	4340	-2697		
Lansing I	4570	-2927		
Hertha	4727	-3084		
B/KC	4754	-3111		
Marm.	4798	-3155		
Pawnee	4856	-3213		
Cherokee	4914	-3271		
Miss.	4938	-3295		
RTD	5010			
LTD	5008			
PBD	4999			
Ran O.H. Logs				
DST #1, 4040-78' (Up. Douglas), misrun-flush tool				
DST #2, 4925-5010' (Miss.), w/results as follows:				
IFP/30": 93-93#				
ISIP/60": 1115#				
FFP/60": 93-93#, GTS in 35", 9 incr. to 17 MCFD				
FSIP/120": 1115#				
Rec: 65' GCM				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS,

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS District Geologist FOR TXO PRODUCTION CORP.  
 OPERATOR OF THE Z-Bar Cattle Co. LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. "A" #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 26th DAY OF May 1981, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold R. Trapp

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10th DAY OF November 1981

**PAMELA S. JOLLIFF**

STATEWIDE  
 NOTARY PUBLIC  
 Harvey County, Ks.

My Appt. Expires 9/14/83

Pamela S. Joliff  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 9/14/83