

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92  
RECEIVED  
STATE CORPORATION COMMISSION

DEC 02 1993

12-2-93

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 7-21-69 Drill Date (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549 (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE UHL "A" WELL# 1 SEC. 11 T. 31S R. 18 (East/West)

- - SE - NW SPOT LOCATION/QQQQ COUNTY Comanche

1980 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1830 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1069' CEMENTED WITH 600 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5192' CEMENTED WITH 160 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5008-16

ELEVATION 2131 GL T.D. 5195 PBSD 5167 ANHYDRITE DEPTH 1045-1070  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU. TIH w/1 1/4" tbg to 5030'. Ld hole w/9 ppg mud. Spot 10 sxs cmt plug from 5030-4910'. TOH w/tbg. Pull 4 1/2" csg. Shoot off at free point. Spot 25 sxs cmt plug at cut off point. Spot 35 sxs cmt plug from 1119-1019'. Spot 10 sxs cmt plug 34-4'. Cut off 8 5/8" csg 4' below ground level & cap. Restore location.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?

If not explain why? Drillers log filed

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE# (316) 624-6253

ADDRESS 1707 W. 2nd Street City/State Liberal, Kansas 67901

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151 (contractor's)

ADDRESS Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/30/93 AUTHORIZED OPERATOR/AGENT: David W. Kapple (signature)

David W. Kapple, Division Production Engineer

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

December 2, 1993

Anadarko Petroleum Corporation  
P. O. Box 351  
Liberal KS 67905-0351

Uhl "A" #1  
API 15-033-20,056-0000  
1980 FNL 1830 FWL  
Sec. 11-31S-18W  
Comanche County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760