

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION

SEP - 1 1989

9-1-89

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM

(File One Copy)

COMPLETION DATE 15-033-20103-0000

~~API#~~ NUMBER 11/11/71 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549 8/90

ADDRESS P.O. Box 351, Liberal, KS 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Dillinger "A" WELL NO. 2 WELL LOCATION C NW SW COUNTY Comanche

SEC. 10 TWP. 31S RGE. 18 (X) or (W) TOTAL DEPTH 5205' PLUG BACK TD 5168'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 525' CEMENTED WITH 390 SACKS

CASING SIZE 4 1/2" SET AT 5200' CEMENTED WITH 150 SACKS

PERFORATED AT 4985'-95'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 30 sxs cmt 5200'-4900', load hole with mud & hulls, shoot off csg @ FP, pump mud & hulls to 600', spot 50 sxs cmt 600'-400', pump mud & hulls to 40', spot 10 sxs cmt 40'-0', cut off csg & cap well 3' below ground level.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Drillers Log
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon Approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P.O. Box 351, Liberal, KS 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 8/90

ADDRESS P.O. Box 506, Liberal, KS 67905-0506 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease

M. L. Pease (Operator or Agent)
Division Production Manager

DATE: 8/30/89

①



15-033-20103-0000

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

DEC 6 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

September 6, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351

Dillinger "A" 2
C NW SW
10-31-18W
Comanche County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760