

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-033-20,759-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Timmons WELL NO. 1 WELL LOCATION E/2 SW COUNTY Comanche

SEC. 6 TWP. 31S RGE. 18 (~~E~~ or (W) TOTAL DEPTH 5235' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A x SWD or INJ WELL _____ DOCKET NO. _____

Conductor
SURFACE CASING SIZE 13 3/8" SET AT 257.29' CEMENTED WITH 295 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD x POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 1170'-50 sx. 2nd plug at 270'-75' sx. 3rd plug at 40'-10 sx. Rathole-10 sx. Mousehole-15 sx. Water well-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 10:30 p.m. on 9-30-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harvey Moore PHONE # (316) 995-4955

ADDRESS Box 163, Belpre, KS 67519

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: October 17, 1989

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1989
10-17-89
CONSERVATION DIVISION
Wichita, Kansas