

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 007-21,151-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corporation KCC LICENSE # 5506
(owner/company name) (operator's)

ADDRESS 107 N. Market Suite 600 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # 316) 267-4379

LEASE Z-Bar WELL# B-1 SEC. 2 T. 35 R. 15 (East West)

-NW -NW -SW SPOT LOCATION/QQQQ COUNTY Barber

2310 FEET (in exact footage) FROM S (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE 16" SET AT 60' CEMENTED WITH N/A SACKS

SURFACE CASING SIZE 8 5/8" SET AT 416' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4972' CEMENTED WITH 175 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4910' - 4918' & 4902' - 4908'

ELEVATION 1538'/1550' T.D. 4970' PBDT 4947' ANHYDRITE DEPTH 950'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4858'. Dump 4 sax cement w/bailer.

Cut & pull 4 1/2. From Surface pump 300# hulls + 10 sax gel + 50 sax cement + 10 sax gel + 100# hulls + 8 5/8" plug + 100 sax cement

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# 316 886-5606

ADDRESS P.O. Box 168 City/State Medicine Lodge, Kansas

PLUGGING CONTRACTOR Clarke Corporation KCC LICENSE # 122270
(company name) (contractor's)

ADDRESS Medicine Lodge, Kansas PHONE # (316) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-8-97 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)

6/97

RECEIVED
KANSAS
CORPORATION
COMMISSION
APR 9 1997
PH 1111

31056/97



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 10, 1997

Woolsey Petroleum Corporation
107 N Market Suite 600
Wichita KS 67202

Z-Bar B-1
API 15-007-21, 151-0000
2310 FSL 330 FWL
Sec. 02-35S-15W
Barber County

Dear Carl W. Durr,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760