

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-173-01549-0000

WELL PLUGGING RECORD

Sedgwick County, Sec. 22 Twp. 27S Rge. 1W (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW NW NW

Lease Owner A. D. Allison & Company, Inc.

Lease Name Benson Well No. 1

Office Address 3212 East Kellogg - Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced _____ June 6 19 57

Plugging completed _____ June 8 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2845 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	150'	None
				5-1/2"	2810'	2539'
				Open hole plugged back to 2810' and casing was perforated at 2780'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 2810' to 2770' and ran 6 sacks of cement. Bailed and mudded the hole to 200', set a 10' rock bridge and ran 25 sacks of cement. Mudded the hole to 25', set a 10' rock bridge and ran 5 sacks of cement on top. Plugging completed.

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet.)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

J. A. Allison (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Allison

(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 57

My commission expires 10-15-1959 Scott Sturkey Notary Public.

PLUGGING
FILE SEC 22T 27R 1W
BOOK PAGE 18 LINE 12

LOCATION: SW NW NW

SEC: 22 TWP: 27 RGE: 1W

FARM: BENSON NO. 1

CASING RECORD:

COMPANY: A. D. Allison & Co., Inc.

8-5/8 150

CONTR: A. D. Allison & Co., Inc.

5-1/2 2810

COMM: 5-29-50

PROD: 40 B O P D

FORMATION

DEPTH

Clay	20
Sand	55
Clay	65
Shale	300
Shale and lime-	575
Lime	650
Shale and shells	725
Lime	850
Lime and shale	1040
Lime and shale	1155
Shale	1360
Shale and shells	1460
Shale	1690
Shale and shells	2330
Shale and shells	2683
Kansas City lime	2795
Lime	2810

TOTAL ROTARY DEPTH 2810

Lime 2845

TOTAL CABLE TOOL DEPTH 2845

TOPS:

Lansing Kansas City 2677

Certified true copy of drillers log.

By A. D. Allison

PLUGGING
FILE SEC. 22 T. 27 R. 1W
BOOK PAGE 18 LINE 12

STATE CORPUS JUDICIAL COMMISSION

JUN 19 1957

CONSERVATION DIVISION

Wichita