

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-033-20091-0000

API NUMBER NA

LEASE NAME DILLINGER "A"

WELL NUMBER 1

1980 Ft. from S Section Line

3250 Ft. from E Section Line

SEC. 10 TWP. 31S RGE. 18 (N) or (W)

COUNTY Comanche

Date Well Completed 4/21/71

Plugging Commenced 10/23/89

Plugging Completed 10/26/89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 6, 1989 (date)

by Shari Feist Albrecht (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4979 Bottom 4984 T.D. 5010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	Oil	4979	4984	8 5/8	538	0
				4 1/2	5009	4305

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot 20 sxs Class "H" cmt 5000'-4800', shot off csg @ 4305'. Load hole w/mud, spot 50 sxs Class "H" cmt 1000'-900', spot 40 sxs Class "H" cmt 560'-460'. Pmpd 10 sxs Class "H" cmt 40'-0' Cut off csg & cap 3' below GL. (Mud & hulls spotted btw cmt plugs).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P. O. Box 506, Liberal, Kansas 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

M. L. Pease (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease
M. L. Pease - Division Production Mgr.

(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
STATE CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this

DEC - 7 1989

12-7-89

CONSERVATION DIVISION
Wichita, Kansas

Commission Expires:

6th day of December, 19 89

Cheryl Steers

Notary Public

