

API NUMBER 15-033-20,089-0000

LEASE NAME Doig "A"

WELL NUMBER 2

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 10 TWP. 31S RGE. 18 ~~XX~~ or (W)

COUNTY Comanche

Date Well Completed 3/20/71

Plugging Commenced 11/10/94

Plugging Completed 11/15/94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/15/94 (date)

by Richard Lacey, (KCC District Agent's Name).

Drillers

Is ACO-1 filed? Log Filed If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 5216'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	509'	3'
				4 1/2	5216'	2630'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pmpd 1 sk hulls & 20 sxs cmt plug to 4900. Displ w/mud. Shot 4 1/2" csg @ 4044', 3033', & 2630' pulled free. Ld 1500' csg. Pull csg to 1100'. Spot 50 sxs cmt plug from 1100-1000'. TOH & spot 50 sxs cmt plug from 550-450'. TOH & spot 10 sxs cmt plug from 40-0'. Cut off 8 5/8" csg 3' below gl & cap. Witnessed by KCC Rep - Richard Lacey.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. _____

Address Rt 1, Box 49BA, Tyrone, Oklahoma 73951-9731 (405) 954-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Leslie I. Barnes, Sr. Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leslie I. Barnes


Leslie I. Barnes, Sr. Tech. Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1994

C Cheryl Steers

My Commission Expires: _____



15-033-20089-0000

RECEIVED
KANSAS CORPORATION COMMISSION

8-8-94
AUG 08 1994

DRILLER'S LOG

WELL NAME Doig "A" No. 2 COMPANY OPERATING Anadarko Production Company
 ADDRESS OF COMPANY Box 351 Liberal, Kansas 67901
 WELL LOCATION C 1/4 NE 1/4 SE 1/4
1980 Ft. North of South Line,
4597 Ft. East of West Line, Sec. 10, Twp. 31S, Rge. 18W, Comanche County, Kansas
 DRILLING STARTED 2-8, 19 71, DRILLING COMPLETED 2-20, 19 71
 WELL COMPLETED 3-20, 19 71, WELL CONNECTED _____, 19 _____
 ELEVATION 2121.0 Ft. Ground Level CHARACTER of WELL (Oil, Gas, Dry Hole) Oil

CONSERVATION DIVISION
WICHITA, KS

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippi	5018	5026	16	Acidized w/750	Mod 202

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	509'	400	NONE
4 1/2"	5216'	150	NONE
2 3/8"	5030'	S.N. @ 5014'	NONE

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface Sand & Clay	.0	235			
Red Bed	235	385			
Shale	385	1318			
Lime & Shale	1318	2325			
Lime	2325	4500			
Lime & Shale	4500	4625			
Lime	4625	4700			
Cherty Lime	4700	5197			
Cherty & Lime	5197	5225			
TOTAL DEPTH	5225				

RESULTS OF INITIAL PRODUCTION TEST: In 6 hrs. swabbed 40 B. O.