

15-019-26629-00-00

CMTTK

# BLUE STAR ACID SERVICE, INC.

PO Box 103  
Eureka, Kansas 67045

Cementing Ticket  
and Invoice Number

## Nº 5426

Date <b>4-9-04</b>	Customer Order No.	Sect. <b>2</b>	Twp. <b>32S<sup>0</sup></b>	Range <b>10E</b>	Truck Called Out	On Location <b>5:20 pm</b>	Job Began <b>5:40 pm</b>	Job Completed <b>6:00 pm</b>
Owner <b>C &amp; E OIL</b>		Contractor <b>C &amp; G DRILLING</b>			Charge To <b>C &amp; E OIL</b>			
Mailing Address <b>RRI Box 1B2</b>		City <b>Moline</b>			State <b>Ks</b>			
Well No. & Form <b>Rodgers SWD Redrill</b>		Place <b>CHAUTAUGUA</b>			State <b>Ks</b>			
Depth of Well <b>53'</b>	Depth of Job <b>51'</b>	Casing <input checked="" type="checkbox"/> (New) <input type="checkbox"/> (Used)	Size <b>8 5/8</b>	Weight <b>24 #</b>	Size of Hole Amt. and Kind of Cement <b>40 SKS</b>	Cement Left in casing by ) <input checked="" type="checkbox"/> Request Necessity <b>10'</b> feet		
Kind of Job <b>SURFACE</b>					Drillpipe	Rotary ) Cable )		Truck No. <b>#21</b>

Price Reference No.	<b># 1</b>
Price of Job	<b>425.00</b>
Second Stage	
Mileage <b>307</b>	<b>67.50</b>
Other Charges	
Total Charges	<b>492.50</b>

Remarks **SAFETY Meeting: Rig up to 8 5/8 CASING. BREAK Circulation with Fresh water. Mixed 40 SKS Regular Cement with 3% CaCl2. Displace with 2 BBL fresh water. SHUT CASING IN. Good Cement Returns to SURFACE. Job Complete. Rig down.**

Cementor **Kevin McCoy**  
Helper **Mike - Russ**

District **EUREKA** State **Ks**

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

**THANK YOU**

**Called By Duke (C & G DRILLING)**  
Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
<b>40 SKS</b>	<b>REGULAR CLASS "A" Cement</b>	<b>7.75</b>	<b>310.00</b>
<b>112 #</b>	<b>CaCl2 3%</b>	<b>.35</b>	<b>39.20</b>
<b>RECEIVED</b>			
<b>AUG 13 2004</b>			
<b>KCC WICHITA</b>			
Plugs	<b>40 SKS</b> Handling & Dumping	<b>.50</b>	<b>20.00</b>
	<b>1.88 Tons</b> Mileage <b>30</b>	<b>.80</b>	<b>60.00 m/c</b>
	Sub Total		<b>921.70</b>
	Delivered by Truck No. <b>#29</b>	Discount	
	Delivered from <b>EUREKA</b>	Sales Tax <b>6.3%</b>	<b>58.07</b>
	Signature of operator <b>Kevin McCoy</b>	Total	<b>989.77</b>

15-019-26629-0000

**BLUE STAR  
ACID SERVICE, INC.**

PO Box 103  
Eureka, Kansas 67045

Cementing Ticket  
and Invoice Number

**Nº 5423**

Date 4-12-04	Customer Order No.	Sect.	Twp.	Range	Truck Called Out	On Location 7:45am	Job Began 9:30am	Job Completed 11:15am
Owner C & E Oil		Contractor C & G Drilling			Charge To C & E Oil			
Mailing Address RR 1 Box 1 B2		City Moline			State Ks.			
Well No. & Form Rogers SWD "Reckill"		Place Chautauqua			State Kansas			
Depth of Well 2115'	Depth of Job 2111'	Casing (New) Size 5 1/2" (Used) Weight 15.5/14.5	Size of Hole 7 3/4"		Amt. and Kind of Cement 340 SKS.		Cement Left in casing by	Request (Necessity) 0 feet
Kind of Job Longstring					Drillpipe	(Rotary)		Truck No. #25
					Tubing	(Cable)		

Price Reference No. \_\_\_\_\_  
 Price of Job 665.00  
 Second Stage \_\_\_\_\_  
 Mileage 67.50  
 Other Charges \_\_\_\_\_  
 Total Charges 732.50

Remarks: Safety Meeting: Rig up to 5 1/2" casing, break circulation with 20 Bbl. fresh water. Mixed 200 SKS 60/40 Pozmix w/ 6% Gel & Floccle. Tailin with 140 SKS Thick Set w/ Floccle 1/4 lb. 1 1/4 SK at 13" lbs. 1 1/4 G.M. Shut down - wash out pump lines - Release Plug Displace Plug with 50 1/2 Bbls. water at 5 1/2 BPM. Final pumping at 900 P.S.I. - Pumped Plug to 1200 P.S.I. check float - float held - wash pump truck out. Rig back up to casing - MIT well at 800 P.S.I. for 30 min. Release pressure - Job complete with Good cement returns to surface with 14 Bbl slurry

Cementor Brad Butler  
 Helper Rick - Alan - Jim - Jason District Eureka State Kansas

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

x Called by Ed  
 Agent of contractor or operator

"Thank you"

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
200	SKS 60/40 Pozmix cement	6.50	1300.00
1000	lbs. Gel 6%	9.50	95.00
50	lbs. Floccle 1/4 lb. 1 1/4 SK	1.00	50.00
140	SKS. Thick Set cement	10.75	1505.00
35	lbs. Floccle 1/4 lb. 1 1/4 SK	1.00	35.00
4	Hrs. 80 Bbl. VAC Truck #20	65.00	260.00
1	load City water	20.00	20.00
1	5 1/2" AFU float shoe	160.00	160.00
2	5 1/2" Centralizers	28.00	56.00
1	5 1/2" Top Rubber Plug	40.00	40.00
	Rotating Head	50.00	N/C
	340 SKS Handling & Dumping	.50	170.00
	15.1 Ton Mileage 30	.80	362.40
	Sub Total		4785.90
	Discount		
	Delivered from Eureka	Sales Tax 6.3%	301.51
	Signature of operator Brad Butler	Total	5087.41