

15-159-00194-0000
WELL PLUGGING RECORD

RICE County. Sec. 16 Twp. 19 Rge. 8W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Sec NW SW

Lease Owner FLYNN OIL COMPANY

Lease Name Plank Well No. 1

Office Address Thompson Building, Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed January 18 19 51

Application for plugging filed January 18 19 51

Application for plugging approved January 18 19 51


Plugging commenced January 18 19 51

Plugging completed January 18 19 51

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee, McPherson, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 3526 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface casing				8 5/8	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole 190' first plug with 15 sacks of cement. Top plug 25 feet with 5 sacks of cement.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 30 1951

CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to: FLYNN OIL COMPANY
 Address: Thompson Building
 Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa ss.
 D.M. Dolphin (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D.M. Dolphin
 Thompson Building, Tulsa, Okla.
 (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January 19 51

My commission expires 2-23-54
 Lula Irene Laessle Notary Public.

22-5133-s 9-48-10M

PLUGGING
 FILE SEC-16 T-19 R-8W
 BOOK PAGE 57 LINE 1

PLANK WELL #1

Casing Record:

8 5/8" - 210'

COMPANY: FLYNN OIL COMPANY

CONTRACTOR: BARBOUR DRILLING CO.

COMMENCED: January 6, 1951

COMPLETED: January 19, 1951

Description: SE NW SW
16-19S-8W
Rice Co.
Kansas

Elevation: 1719' DF
DRY HOLE

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface	0	210	
Shale & shells	210	745	8-5/8" O.D. Casing
Anhydrite	745	765	Cemented with 125 sx.
Shale & shells	765	1130	bulk cement with 200 #
Anhydrite	1130	1155	calcium choloride
Shale & shells	1155	1460	
Shale & lime	1460	2185	
Shale	2185	2490	
Shale & lime	2490	2574	
Lime	2574	2645	
Lime & shale	2645	2895	
Lime	2895	3473	Slight stain & odor at 2939-45 DST #1 Fair Saturation & good odor at 3319-30 DST #2
Chert	3473	3496	
Arbuckle Lime	3496	3502	
Lime	3502	3526 TD	
Top Topeka	2410		<u>DRILL STEM TEST #1</u>
Heebner	2726		Packer set at 2912, TD 2950.
Brown Lime	2865		Open 1 hour. Recovered 22'
Kansas City	2895		slightly oil cut mud. BHP 210
Base " "	3252		<u>DRILL STEM TEST #2</u>
Top Sandy Conglomerate	3319		Packer set at 3318, TD 3330.
Viola	3382		Open 1 hour. Recovered small
Simpson Shale	3437		show gas and 75' heavily oil
Simpson Sand	3446		cut mud and water. BHP 820.
Arbuckle	3496		

I certify that this is a true and correct copy of the above log to the best of my knowledge.

P. M. Dolphin
P. M. Dolphin

Subscribed and sworn to before me this 29th day of January, 1951.

Lula Irene Reese
NOTARY PUBLIC

My Commission Expires
February 23, 1954

PLUGGING
FILE SEC 16 T 19 R SW
BOOK PAGE 57 LINE 1

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1951
CONSERVATION DIVISION
Wichita, Kansas