

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,759-0000

LEASE NAME Timmons

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1320 Ft. from S. Section Line

3300 Ft. from E Section Line

SEC. 6 TWP. 31S RGE. 18 ~~W~~ (W)

COUNTY Comanche

Date Well Completed 9-30-89

Plugging Commenced 10-01-89

Plugging Completed 10-01-89

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-01-89 (date)

by State Plugger, Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5235'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8"	257.29'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Circulate heavy mud in hole. 1st plug from 1170' to 970' w/50 sx. 2nd plug from 270' to surface w/75 sx. 3rd plug from 40' to surface w/10 sx. Rathole-10 sx, mousehole-15 sx. Water well-10 sx
All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1989

My Commission Expires: May 18, 1993

Sharan J. Branstetter Notary Public



KCC OIL/GAS REGULATORY OFFICE

DATE 9/13/90

New Situation
 Response to Request
 Follow-up

OPERATOR Abercrombie Drilling # 5393

NAME 150 N. Main, Suite 801

LOCATION SW, SEC 6, T 31 S, R 18 W

&
ADDRESS Wichita, KS 67202

LEASE Timmons Well # 1

PHONE NO. _____
OPER. _____ OTHER _____

COUNTY Comanche

REASON FOR INVESTIGATION: Landowner complaint

LEASE INSPECTION

PROBLEM: D & A well-cement plug fell 145'. KCC concerned about integrity of other plugs.

PERSON(S) CONTACTED: Jack Partridge, Eddie Abercrombie

FINDINGS: Top plug fell 145'. Required company to re-enter well and drill out to test intermediate plug. Encountered 1st plug at 146', drilled 20' soft cement, washed through to 320', hit soft cement to hard cement at 355'. Pulled tubing to 320' and replugged well back to surface with 185 sx 50/50 Pozmix 4% gel 3% cc. Some loss of fluid at time of washdown. The cement stopped fluid loss.

COMPLAINT

photos taken: _____

ACTION/RECOMMENDATIONS: None. Information only.

FIELD REPORT

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Steve Durrant

SEP 19 1990
9-17-90
CONSERVATION DIVISION
Wichita, Kansas

9/17/90