

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Comanche County, Sec. 6 Twp. 31 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Capitt Drilling, Inc.

Lease Name Burkhall Well No. 1

Office Address 814 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 26 1959

Application for plugging filed October 26 1959

Application for plugging approved October 26 1959


Plugging commenced October 26 1959

Plugging completed October 26 1959

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5157 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	490'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from rotary total depth (5157') to 475'. Set Plug #1 and 20 sacks cement.
Filled hole with extra heavy rotary mud from Plug #1 to 35', Set Plug #2 at 35' with 10 sacks cement. Steel plate welded on surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1959
11-3-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. R. R. McNicol

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 59

My commission expires Sept. 30, 1963 Darlene May Notary Public.



15-033-10011-0000

ROTARY DRILLING LOG

OPERATOR: Capitt Drilling, Inc.
Burkhall No. 1
C NE NE Sec. 6-31S-18W,
Comanche County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 10-6-59
COMP: 10-26-59

Remarks: Set 8-5/8" surface casing at
490' cemented with 325 sacks
HA-500 cement

Formations:

Surface Clay	180'
Red Bed	490'
Red Bed & Lime Shells	613'
Shale & Shells	1808'
Shale & Lime	2105'
Lime	2145'
Lime & Shale	2315'
Lime	5157'
Rotary Total depth (D&A)	5157'

We certify the above log is true and
correct to the best of our knowledge
and belief.

CAPITT DRILLING, INC.

R. R. McNicol
R. R. McNicol

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1959
11-3-59
CONSERVATION DIVISION
Wichita, Kansas