

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 007-21,151-0000

LEASE NAME Z-Bar

WELL NUMBER B-1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 2 TWP. 35s RGE. 15 (W)

COUNTY Barber

Date Well Completed N/A

Plugging Commenced 4-15-97

Plugging Completed 4-18-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Woolsey Petroleum Corp.

ADDRESS 107 N. Market, Suite 600, Wichita, KS 67020

PHONE# (316) 886-5606 OPERATORS LICENSE NO. 5506

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-15-97 (date)

by Steve Piefer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Miss Depth to Top 4902 Bottom 4918 T.D. 4970

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				16	60	None
				8 5/8	416	None
				4 1/2	4972	3400

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set Lay down rods and tubing, sand well back to 4754, dump 4sx portland cement with dump bailor, stretch and cut pipe at 3400, lay down casing, Allied pump 300 hulls, 10 jel, 50 cement, 10 jel 100 hulls, 100 cement, 60/40 6% jel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Corp.


STATE OF Kansas COUNTY OF Barber, ss.

RECEIVED
KANSAS CORP COM
4-29-97
1997 APR 29 4:11:42 PM

Alan Vratil (Employee of Operator) of (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 23 day of April, 1997

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98