

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Barber County, Sec. 25 Twp. 30S Rge. (R) 11 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE  
Lease Owner Murfin Drilling Company  
Lease Name Westerman Well No. 1  
Office Address 617 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 9, 1973  
Application for plugging filed June 9, 1973  
Application for plugging approved June 9, 1973  
Plugging commenced June 9, 1973  
Plugging completed June 9, 1973  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4772 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	309'	None
RECEIVED STATE CORPORATION COMMISSION JUN 13 1973 6-13-73 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 250 feet. Followed by wooden plug and 1/2 sack hulls. Placed 25 sacks onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 11th day of June, 1973

Betty Brandt  
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Murfin Drilling Company DRILLING COMMENCED: May 29, 1973  
617 Union Center  
Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: June 9, 1973  
505 Union Center  
Wichita, Kansas 67202

CASING RECORD: 14 Jts. 309' - 8-5/8" LOCATION: Westerman No. 1  
cemented with 275 sacks. C NW NE  
Section 25-30S-11W  
Barber County, Kansas

0 - 125	Sand
125 - 1660	Red bed & shale
1660 - 2210	Shale & lime
2210 - 2725	Lime & shale
2725 - 2945	Shale & lime
2945 - 3155	Lime & shale
3155 - 3325	Shale & lime
3325 - 3635	Lime & shale
3635 - 3840	Shale & lime
3840 - 3905	Lime & shale
3905 - 4045	Lime
4045 - 4445	Lime & shale
4445 - 4670	Shale
4670 - 4760	Lime
4760 - 4772	Sand
4772	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 13 1973  
6-13-73  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President

STATE OF KANSAS )  
                          ) ss.  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, this 12th of June, 1973.

My commission expires:  
May 9, 1975

Betty Brandt  
Notary Public