

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-22,383-0000

LEASE NAME ECKLES

WELL NUMBER 1-3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1980 Ft. from S Section Line

660 Ft. from E Section Line

C NE SE

SEC. 3 TWP. 30 RGE. 13 ~~XX~~ or (W)

LEASE OPERATOR F G HOLL COMPANY

ADDRESS 6427 E. KELLOGG P O BOX 780167 WICHITA, KS. 67278-0167 COUNTY BARBER

PHONE#(316 684-8481 OPERATORS LICENSE NO. 5056

Date Well Completed _____

Character of Well OIL

Plugging Commenced OCT. 1, 1992

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed OCT. 7, 1992

The plugging proposal was approved on OCTOBER 5, 1992 (date)

by STEVE MIDDLETON DODGE CITY OFFICE (KCC District Agent's Name).

Is ACO-1 filled? YES If not, Is well log attached? _____

Producing Formation MARMATON Depth to Top Section 4621 T.D. 4675

P.B.T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	232	13 3/8	232'	0
		0	4669	4 1/2	4469	2574' - 61 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

10-1-92: RIGGED UP, PULLED 170 X 3/4 RODS & 140 X 2 3/8" TUBING
10-2-92: DUMPED 7 BBL'S OF SAND, COVERED TOP PERFS + 50 FT. ABOVE PERFS.
10-5-92: DUMPED 4 SX CEMENT & SHOT CASING OFF AT 2574, PULLED & LAYED DOWN 61 JTS. OF CASING.
10-7-92: HALLIDURTON TOP HOLE PLUGGED WITH 400# HULLS, 275 SX CEMENT, 20 SX GEL. 6%, 60-40 POZ.
 (If additional description is necessary, use BACK of THIS form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F G HOLL CO.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

RECEIVED
 OCT 9 1992
 10-9-92
 CONSERVATION DIVISION
 Wichita, Kansas
 PLUGGING CONTRACTOR

(Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO W.S. Inc.



SUBSCRIBED AND SWORN TO before me this 8th day of October, 1992

My Commission Expires Feb. 3, 1993

Notary Public

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- ECKLES #1-3
 Located: C NE SE, Section 3-30S-13W, Barber County,
 Kansas

OWNER: F. G. Holl Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 12, 1991

COMPLETED: November 23, 1991

TOTAL DEPTH: 4675'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 80 Surface Soil and Clay	Ran 5 joints 13 3/8", 40# new casing. 222.71' pipe set at 232' K.B. Cemented with 250 sacks Common, 2% gel and 3% cc. Plug down at 3:00 PM, 11-12-91, by Howco.
80 - 235 Red Bed	
235 - 1930 Shale	
1930 - 4675 Lime and Shale	Ran 111 joints 4 1/2", 10 1/2# used casing. 4674.74' pipe set at 4669' K.B. Cemented with 20 bbl. salt flush, 20 bbl. super flush ahead of 100 sacks Lite, 125 sacks F. G. Holl mix. Plug down at 12:45 PM, 11-23-91, by Howco.

RECEIVED
 KANSAS CORPORATION COMMISSION

Deviation Surveys: 3/4° at 4445'
 7/8° at 4556'

AUG 31 1992
 8-31-92
 CONSERVATION DIVISION
 WICHITA, KS