


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 3 Twp. 30S Rge. 13W (E) (W)
Location as "NE/CNWxSWx" or footage from lines C S/2 SE SE
Lease Owner Bachus Oil Company
Lease Name Keyes Well No. 1
Office Address 415 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 20 19 57
Application for plugging filed December 20 19 57
Application for plugging approved December 20 19 57
Plugging commenced December 20 19 57
Plugging completed December 20 19 57
Reason for abandonment of well or producing formation no oil in commercial quantities found
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4687 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	317'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 300'. Set Plug #1 with 20 sacks. Filled hole with extra heavy rotary mud from Plug #1 to 35'. Set Plug #2 at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1957
12-26-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of December, 19 57

Darlene May
Notary Public.

My commission expires September 30, 1959

PLUGGING
FILE SEC 3 T 30 R 13W
BOOK PAGE 71 LINE 17

ROTARY DRILLING LOG

OPERATOR: Bachus Oil Company
 Keyes No. 1
 C S/2 SE SE Sec. 3-30S-13W,
 Barber County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 11/30/57
 COMP: 12/20/57

Remarks: Set 8-5/8" surface casing
 at 317' cemented with 250 sacks
 Pozmix, 2% C.C.

Formations:

Surface Clay & Sand	110'
Red Bed	835'
Red Bed, Shale & Shells	1100'
Shale & Shells	1810'
Lime & Shale	2725'
Shale & Lime	3060'
Lime & Shale	3195'
Shale & Lime	3315'
Lime	3632'
Lime & Shale	3815'
Shale & Lime	3857'
Lime	4302'
Lime & Chert	4363'
Shale, Lime & Chert	4418'
Lime & Chert	4520'
Lime & Shale	4534'
Lime & Chert	4540'
Lime & Shale	4561'
Lime	4592'
Shale, Streaks Lime	4641'
Lime & Shale	4658'
Lime	4687'
Rotary Total Depth (D&A)	4687'

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol

RECEIVED
 STATE CORPORATION COMMISSION
 12-26-57
 DEC 26 1957

DIVISION

PLUGGING
 FILE SEC 3 T30R13W
 BOOK PAGE 71 LINE 17