


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 3 Twp. 30S Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines NE/4 NE/4 SW  
Lease Owner Schermerhorn Oil Corporation  
Lease Name Levens Well No. 1  
Office Address P. O. Box 287, Tulsa 1, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 12 19 61  
Application for plugging filed April 12 19 61  
Application for plugging approved April 12 19 61  
Plugging commenced April 12 19 61  
Plugging completed April 13 19 61  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation Depth to top Bottom Total Depth of Well 4660 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	963'	8-5/8"		
	956.14'					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged as follows: Plugged at 300' with 15 sacks of cement and 1/4 sack of hulls. Cement through drill pipe and mud to 35'. Plugged at 35' with 10 sacks of cement and 1/4 sack of hulls. Two sacks of cement in rat-hole. Plug down at 1:30 A. M. 4-13-1961.

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 1961  
4-17-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss. Elmer Savage (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer Savage  
Elmer Savage  
2401 Walnut Drive, Gt. Bend, Kans  
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1961

My commission expires December 14, 1961

Elaine H. Taylor  
Elaine H. Taylor Notary Public.



D R I L L E R S   L O G

#1 Levens

CASING RECORD: 956.14' of new 8- 5/8" surface casing	COMPANY: Schermmerhorn & Kenwood Oil Company	DESCRIPTION: NE NE SW Section 3-30S-13W
TOTAL DEPTH: 4660'	CONTRACTOR: Strata Drilling, Inc.	Barber County, Kansas
	COMMENCED: March 29, 1961	ELEVATION: 1861' RB 1856' GR
	COMPLETED: April 13, 1961	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	40	Ran 956.14' of new 8-5/8" surface casing; set and cemented at 963' with 475 sacks of cement, 6% gel. Lost circ. recemented with 275 sacks of cement, 2% C. C. through 100' 1" pipe. Job completed at 3:30 P. M. March 30, 1961.
Sand	40	130	
Red Bed & Shells	130	760	
Shale & Shells	760	966	
Shale	966	1840	
Lime & Shale	1840	3560	
Lime & Chalk	3560	3665	
Lime & Shale	3665	3805	
Shale & Sand	3805	3872	
Lime	3872	4315	
Lime & Shale	4315	4341	DST #1 4299'-4341'; tool open 1 hr., gas to surface 40 min, TSTM. Recovered 55' gas cut mud. IBHP 840 lbs. in 20 min. IFP 0 lbs. FFP 0 lbs. FBHP 540 lbs. in 20 minutes.
Lime & Chert	4341	4378	
Lime & Shale	4378	4400	
Chert & Dolomite	4400	4460	
Lime	4460	4552	DST #2 4444'-4460'; tool open 30 min., weak blow 25 minutes. Recovered 25' mud. All pressures werer 0 lbs.
Lime & Shale	4552	4566	
Sand	4566	4586	
Lime & Sand	4586	4595	
Lime & Shale	4595	4660	DST #3 4460'-4485'; tool open 1 hr., gas to surface 5 minutes. Gauged 365,000 cubic feet declined to TSTM in 20 minutes. Recovered 60' heavily oil cut mud, 60' muddy oil. IBHP 1090 lbs. in 20 min. IFP 60 lbs. FFP 60 lbs. FBHP 160 lbs. in 20 minutes.
Total Depth 4660'			
Top Anhydrite	752'		
Top Heebner	3683'	(-1822')	
Top Toronto	3698'	(-1837')	
Top Douglas	3721'	(-1860')	
Top Brown Lime	3869'	(-2008')	
Top Lansing	3883'	(-2022')	
Top Mississippi	4311'	(-2450')	DST #4 4552'-4577'; tool open 45 min., weak blow 27 minutes. Recovered 30' mud. IBHP 460 lbs. in 20 minutes. IFP 0 lbs. FFP 0 lbs. FBHP 0 lbs.
Top Kinderhook	4380'	(-2519')	
Top Misener	4439'	(-2578')	
Top Viola	4448'	(-2587')	
Top Simpson	4551'	(-2690')	DST #5 4580'-4595'; tool open 1 hour, fair blow throughout test. Recovered 450' water. IBHP 1160 lbs. in 20 min. IFP 40 lbs. FFP 205 lbs. FBHP 1040 lbs. in 20 minutes.
Top Arbuckle	4652'	(-2791')	

**RECEIVED**  
STATE CORPORATION COMMISSION

APR 17 1961  
4-17-61  
CONSERVATION DIVISION  
Wichita, Kansas

Ran Schlumberger Log.

D. & A.

Plugged as follows: Plugged at 300' with 15 sacks of cement, 1/4 sack of hulls. Cement through drill pipe and mud to 35'. Plugged at 35' with 10 sacks of cement, 1/4 sack of hulls. Two sacks of cement in rat-hole. Plug down at 1:30 A. M. 4-13-1961.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Jim B. McWilliams*  
Jim B. McWilliams, Secy-Treas.

Drillers Log  
#1 Levens  
Page Two

Subscribed and sworn to before me this 14th day of April, 1961.

Elaine H. Taylor  
Elaine H. Taylor, Notary Public

My Commission Expires:  
December 14, 1961

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 1961  
4-17-61  
CONSERVATION DIVISION  
Wichita, Kansas