

API NUMBER 007,22,236-0000

LEASE NAME Lambert C

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 30S RGE. 13 (E) or (W)

COUNTY Barber

Date Well Completed 5-897

Plugging Commenced 12-31-96

Plugging Completed 01-02-97

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 N. Main Suite 1000, Wichita, Kansas 67202

PHONE (316) 262-3596 OPERATORS LICENSE NO. 9408

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 01-02-97 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top 4415 Bottom 4455 T.D. 4790

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			8 5/8"	927	0
	Production			5 1/2"	4787	2806

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
 Bottom plug; sanded off to 4365' 5 sks of cement. Allied mixed 300 lbs. C.S. hulls, 1000 lbs. gel 50 sks of cement. 1000 lbs gel 100 lbs. CS hulls. Released plug, mixed 100 sks 60/40 poz. Down 8 5/8" Maximum 100 sks 60/40 down Annulus 10 3/4 x 8 5/8"

Name of Plugging Contractor D.S. & W. Well Servicing, Inc. License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans Pacific Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.

Joseph J. Strube (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Joseph J. Strube


(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 6th day of January, 19 97

Karlynn K. Beck
 Notary Public

My Commission Expires: 09-28-98

USE ONLY ONE SIDE OF EACH FORM



15-007-22236-0000

ORIGINAL

Trans Pacific Oil Corporation
410 One Main Place
Wichita, Kansas 67202

RELEASED

SEP 2 5 1990

DRILLERS LOG

FROM CONFIDENTIAL

1 Lambert C
N1/2 SE NE 5-30S-13W
Barber County
Kansas

Spud Date: 04-22-89
Comp. Date: 05-02-89

0-321'	Surface Clay
321-877'	Shale & Sand
877-1525'	Red Bed & Shale
1525-2360'	Shale & Lime
2360-3020'	Lime & Shale
3020-3585'	Shale & Lime
3585-4080'	Shale & Lime
4080-4490'	Shale & Lime
4490-4649'	Shale & Lime
4649-4675'	Shale & Sand
4675-4790'	Shale & Lime
4790-	T.D.

RECEIVED
STATE CONSERVATION COMMISSION
MAY 24 1989
5-24-89
CONSERVATION DIVISION
Wichita, Kansas.

Surface Casing : Ran 8 jts used 10 3/4" set @316'
Cemented w/225 SXS 60/40 POZ 3% CC 2% GEL

Conductor Casing : Set 22 jts 8 5/8" 24# set @927'
Cemented w/100 SKS 60/40

Production Casing : Ran 117 JTS 3 1/2" casing set @4787'
Cemented w/50 SXS 60/40

AFFIDAVIT

STATE OF KANSAS
COUNTY OF SEDGWICK

Alan D. Banta of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Alan D. Banta
Alan D. Banta

Subscribed and sworn to before me this 23rd day of May 19 89

My Commission Expires: Sondra J. Follis
Notary Public
Sondra J. Follis

May 13, 1991