

API NUMBER 15-007-7076-000

LEASE NAME Hildreth

WELL NUMBER 1-5

SPOT LOCATION _____

SEC 5 TWP 30S RGE 13 West or

COUNTY Barber

Date Well Completed _____

Plugging Commenced 4-17-87

Plugging Completed 4-18-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4760

Perfs: 4611-19 PBTD 4626
Show depth and thickness of all water, oil and gas formations. Top of cement 3900-4000'.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	302'	0
				4 1/2"	4478'	83 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

4-17-87 : Dumped 110 gal. of sand, + 12 bbls. of water, pumped another 70 bbls. of water on top.

4-18-87: Dumped 4 sx. shot off casing at 3573', recovered 83 jts. jts. Rigged down and moved off. Top hole plugging on 4-22-87: 2 hulls, 15 gal, 50 sx. 10 gal, 1 hull, 8 5/8" plug, 135 sx. cement. 60-40 cc, 63 gal. 500# pumping pressure, ISIP 350#, 11:00 A.M.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.


Judy Berry

(employee of ~~owner~~ plugging contractor)

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 Pratt, Ks. 67124



SUBSCRIBED AND SWORN TO before me, STATE CORPORATION COMMISSION, June 1, 1987

My Commission expires: February 6, 1989

Dorothy M. Furgason
Notary Public
6-3-87
CONSERVATION DIVISION
Wichita, Kansas

15-057-20760-0000
WELL LOG

COMPANY F. G. Holl

BED. 5 T. 30S R. 13W

FARM Hildreth

NO. 1-5

LOC. C SW NE


TOTAL DEPTH 4780'

COUNTY Barber

COMM. 6-24-79

COMP. 7-2-79

CONTRACTOR DaMac Drilling Inc.



CASING 8 5/8 set @ 302

ELEVATION

PRODUCTION 4 1/2 @ 4780

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Sand, Shells, Shale	0	170
RedBed	170	302
RedBed, Shale	302	2060
Shale	2060	2255
Lime, Shale	2255	4700
Lime	4700	4780 RTD