

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-159-19285-0001

API NUMBER E-13,839

LEASE NAME Bell

WELL NUMBER 33-2

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 33 TWP. 19S RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed 63

Plugging Commenced 12-12-89

Plugging Completed 12-12-89

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE#( ) 522-1560 OPERATORS LICENSE NO. 5822

Character of Well inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-12-89 (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? N/A

Producing Formation Kinderhook Depth to Top 3347 Bottom 3358 T.D. 3388

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	208	8 5/8	208	None
		0	3424	5 1/5	3424	1861

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Sand back to 3280 ft spot 5 sacks cement, pulled casing to 1150 ft pumped  
75 ft plug, pulled to 750 ft, pumped 75 ft plug, pulled to 260 ft, circulated  
cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam

(Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of these facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) K Todd Allam

(Address) Haysville, Ks. 67060

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1989

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of December, 19 89

Gary D. Stearns  
Notary Public

My Commission Expires:

GARY D. STEARNS

NOTARY PUBLIC

STATE OF KANSAS

My Appt. Exp. 2-19-92



Form CP-4  
Revised 05-88

GARDNER-JONES INC.  
WICHITA, KANSAS  
DRILLERS WELL LOG

BELL #2  
C SW NW SECTION 33-19S-8W  
RICE COUNTY, KANSAS

COMMENCED: JULY 20, 1963  
COMPLETED: JULY 27, 1963

OPERATOR - O. A. SUTTON

DEPTH		FORMATION	REMARKS
FROM	TO		
0	208	CLAY	RAN 10 JOINTS 8-5/8" CASING, SET @ 208' W/ 185 BAGS CEMENT
208	290	RED BED	
290	305	ANHYDRITE	
305	1310	SHALE & SHELLS	
1310	2740	LIME, SHALE	
2740	3342	LIME	
3342	3365	CORE	
3365	3425	LIME, SHALE	
3425	TD		RAN 105 JOINTS 5-1/2" CASING, SET @ 3424 W/ 75 BAGS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C SW SW SECTION 33-19S-8W, RICE COUNTY, KANSAS TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall  
E. E. HALL

STATE OF KANSAS        }  
COUNTY OF SEDGWICK } SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 29TH DAY OF JULY, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES HTEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie  
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963

RECEIVED  
STATE CORPORATION COMMISSION

AUG 22 1963

CONSERVATION DIVISION  
Wichita, Kansas