

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-19284-000

LEASE NAME Bell

WELL NUMBER 33-1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 33 TWP. 19 RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-17-89

Plugging Completed 8-17-89

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE# ( ) 522-1560 OPERATORS LICENSE NO. 5822

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-17-89 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? w/cp-1

Producing Formation kinderhook Depth to Top 3315 Bottom 3384 T.D. 3346

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	212	8 5/8	212	0
		0	3384	5 1/2	3384	2520'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand back to 3260' and spot 6 sacks cement, pulled pipe to 1150' and pumped 75' plug, pulled pipe to 750' and pumped 75' plug, pulled to 270' and pumped cement to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Copr. License No. 5822

Address Box 322 Haysville Ks. 67060

RECEIVED

STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Corp.

STATE OF Kansas COUNTY OF Sedgwick

SEP 12 1989

ss.

K. Todd Allam

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) K Todd Allam

(Address) Box 322 Haysville, Ks. 67060

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 89

Darryl D. Stearns  
Notary Public

My Commission Expires:



WICHITA, KANSAS  
DRILLERS WELL LOG

BELL #1  
C NW NW SECTION 33-19S-8W  
RICE COUNTY, KANSAS

COMMENCED: MAY 20, 1963  
COMPLETED: MAY 28, 1963

OPERATOR - O. A. SUTTON

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	212	SURFACE CLAY, SHALE & SHELLS	RAN 10 JOINTS 8-5/8" CASING, SET @ 212' W/ 185' BAGGS CEMENT
212	1010	SHALE	
1010	1500	SHALE & SHELLS	
1500	1805	LIME	
1805	2675	LIME & SHALE	
2675	3145	LIME	
3145	3180	LIME & CHERT	
3180	3312	LIME	
3312	3339	CORE	
3339	3385	LIME & SHALE	
3385	TD		RAN 104 JOINTS 5-1/2" CASING, SET @ 3384' W/ 80 BAGGS CEMENT.


I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NW NW SECTION 33-19S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

  
E. E. HALL

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY, AND STATE ON THIS 31ST DAY OF MAY, 1963, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

  
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963.

RECEIVED  
STATE NOTARY COMMISSION

AUG 22 1963

CONSERVATION DIVISION  
WICHITA, KANSAS