

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-159-20295-0000


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

RICE County. Sec. 5 Twp. 20S Rge. (E) 8W (W)
Location as "NE/CNW/SW" or footage from lines 140' S OF C NW SW
Lease Owner BRADEN DRILLING, INC.
Lease Name KOONS Well No. 4
Office Address 1620 WICHITA PLAZA WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed APRIL 1 19 70
Application for plugging filed FEBRUARY 9 19 72
Application for plugging approved 19
Plugging commenced FEBRUARY 14 19 72
Plugging completed FEBRUARY 16 19 72
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well GILBERT TOMAN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3421 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	209'	NONE
				5 1/2"	3407'	2523.94'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3421' - 3390' - SAND
3390' - 3350' - 5 SACKS CEMENT
3350' - BASE - PUMPED 3 SACKS OF HULLS, @ 20 SACKS OF GEL AND 75 SACKS OF CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF BARTON, ss. T. L. NUTT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
BOX 562 - GREAT BEND, KANSAS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 72

My commission expires July 31, 1974
Mary M. Guesnier
Mary M. Guesnier Notary Public.

4-7-70


COMPANY Braden Drilling, Inc.

SEC. 5 T. 20S. R. 8W
 LOC. 140' S of CNW SW

FARM Koons NO. 4

TOTAL DEPTH 3,410'
 COMM. March 25, 1970 COMP. April 1, 1970
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Rice
 KANSAS



CASING
 20 10
 15 8 5/8" 209' cemented w/200 sx cement ELEVATION 1672 KB
 12 6
 13 5 1/2" 3407' cemented w/75 sx cement PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Shale	100
Red Bed	208
Red Bed, Shale & Shells	650
Shale & Lime	1130
Lime & Shale	1835
Shale & Lime	2420
Lime & Shale	2548
Lime	2690
Shale & Lime	2805
Lime	3020
Shale & Lime	3120
Lime	3255
Sand, Lime & Shale	3338
Lime & Shale	3375
Shale & Lime	3410
Rotary Total Depth	3410

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 11 1972
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer
 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 6th day of April, 1970.

Martha Hartpence
 Martha Hartpence - Notary Public

My Commission Expires:

April 21, 1971

FEB 9 1972

Santa J. Pipe Supply