


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County, Sec. 33 Twp. 19S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines NW/NW/SW
Lease Owner Kewanee Oil Company
Lease Name Truesdell A Well No. 1
Office Address P. O. Box 360, Hoisington, Kansas 67544
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 11, 19 65
Application for plugging filed March 11, 19 65
Application for plugging approved Verbal March 11, 19 65
Plugging commenced March 11, 19 65
Plugging completed March 11, 19 65
Reason for abandonment of well or producing formation Dry Hole.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Verbal from Mr. Gilbert Toman

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	2749		10-3/4"	211'	None
Brown Lime	"	2890				
Lansing Kansas City	"	2924				
Base Kansas City	"	3225				
Litho Lime	"	3308				
Base Litho Lime	"	3339				
Upper Kinderhook Sand	"	3341				
Lower Kinderhook Sand	"	3382				
Maquoketa	"	3430				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from Total Depth to 200'.
Set plug at 200' with 1/2 sack hulls on top. Filled casing with 25 sacks cement to 145'. Filled casing with mud from 145' to 40'.
Set plug at 40' with 1/2 sack hulls on top. Filled casing to surface with 15 sacks cement. 2 sacks cement in rat hole.
Hole plugged at 9:20 P.M. 3-11-65.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1965

03-23-65
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert Jones Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Paul G. Arnold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul G. Arnold
P. O. Box 360, Hoisington, Kansas 67544
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 1965

My commission expires 8-2-65 Notary Public.



GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

TRUESDELL #1A M
 NW NW SW SECTION 33-19S-8W
 RICE COUNTY, KANSAS

COMMENCED: MARCH 2, 1965
 COMPLETED: MARCH 11, 1965

OPERATOR - KEWANEE OIL COMPANY

DEPTH		FORMATION	REMARKS
From	To		
0	30	CLAY	
30	100	CLAY AND SAND	
100	211	SHALE	RAN 7 JOINTS 10-3/4" CASING, SET @ 211' w/200 BAGS CEMENT
211	250	SHALE & RED BED	
250	276	RED BED	
276	290	ANHYDRITE	
290	1780	SHALE & LIME	
1780	2030	SHALE	
2030	2450	SHALE & LIME	
2450	2748	LIME	
2748	2890	SHALE w/ LIME	
2890	3213	LIME	
3213	3235	SHALE & LIME	
3235	3320	SAND, SHALE, LIME	
3320	3370	LIME	
3370	3420	SHALE & SAND (CORE)	
3420	3440	SHALE	
3440	TD		DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1965
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE NW NW SW SECTION 33-19S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 15TH DAY OF MARCH, 1965, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968

REMANEE OIL COMPANY

West Kansas District

Lyons Area

Hell Record and Sandology: Trussdell "A" No. 1.

Location: 330' E11 and W lines of SW/4 Section 33, T-19-S, R-8-W, Rice County, Kansas.

Elevation: 1703' Cement Marker.

Contractor: Gabbart Jones, Inc.

Drilling Commenced: 3-2-65.

Drilling Completed: 3-10-65.

Completion Date: 3-11-65.

Total Depth: 3440" C.M.

PBID: P & A.

Initial Production: None.

Pay Horizon: Kinderhook Sand.

Net Pay: None.

Additional Pays: None.

Perforating Record: None.

Treating Record: None.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1965

CONSERVATION DIVISION
Wichita, Kansas

Formation Tops

Hoebner	2749	-1046
Brown Lime	2890	-1187
Lansing-Kansas City	2924	-1221
Base Kansas City	3225	-1522
Litho Lime	3308	-1605
Base Litho Lime	3339	-1636
Upper Kinderhook Sand	3341	-1638
Lower Kinderhook Sand	3382	-1679
Maquoketa	3430	-1727

Casing Record

Run 209.97' of 10-3/4" casing set at 210.97' Cement Marker. Cemented with 200 sacks regular cement with 1/4# Floccle/sack and 2% CaCl₂. Circulated.

Formation Record

0- 30	Clay
30- 100	Clay and sand
100- 211	Shale
211- 250	Shale and red bed
250- 276	Red bed
276- 290	Anhydrite
290-1780	Shale and lime
1780-2030	Shale
2030-2480	Shale and lime
2480-2748	Lime
2748-2890	Shale w/lime
2890-3213	Lime
3213-3235	Shale and lime
3235-3320	Sand, shale and lime
3320-3370	Lime
3370-3420	Shale and sand (core)
3420-3440	Shale
3440	Total Depth