


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 33 Twp. 19 Rge. 8W (E) 2 (W)
Location as "NE/CNW/SW" or footage from lines C NW NE
Lease Owner Wayne Merchant
Lease Name Blessing Well No. 1
Office Address Beacon Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed November 27, 1965
Application for plugging filed November 27, 1965
Application for plugging approved November 27, 1965
Plugging commenced November 27, 1965
Plugging completed November 27, 1965
Reason for abandonment of well or producing formation D&A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production -- 19--
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3410 Feet
Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	212'	8-5/8"	206.19'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was plugged with mud to 200' and plugged with 1/3 sack hulls and 25 sacks cement. Mud to 42' and plugged with 25 sacks hulls and 10 sacks cement. 2 sacks in rat hole. job completed at 6:30 A.M. November 27, 1965.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden Drilling, Inc.
Address 1620 Wichita Plaza Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. James Tasheff

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Tasheff
1620 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1965

My commission expires October 13, 1969

Marlyn Ann Smith
Notary Public.

DRILLER'S LOG

Wayne Merchant
BLESSING #21
C. NW NE Sec. 33-19S-8W
Rice County, Kansas

Commenced: November 20, 1965
Completed: November 27, 1965

Braden Drilling, Inc., Contractor

Set 8-5/8" casing at 212' with landing
joint and cemented with 165 sacks cement
2% gel and 2% C.C.

<u>Formation</u>	<u>From</u>	<u>To</u>
Surface Clay and Shale	0	125
Anhydrite	125	213
Red bed	213	970
Shale	970	1475
Lime and Shale	1475	2230
Shale and Lime streaks	2230	2400
Shale and Lime	2400	2575
Lime and Shale	2575	2825
Shale and Lime	2825	3053
Lime	3053	3365
Sand and Shale	3365	3401
Sand and Shale	3401	3410 T.D.

I hereby certify that this is a true and correct log of the above
captioned well as shown by the daily drilling reports.


James Tacheff

Subscribed and sworn to before me this 29th day of November, 1965.

My commission expires October 13, 1969


Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1965

CONSERVATION DIVISION
Wichita, Kansas