


15-159-02923-0000  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rice County. Sec. 33 Twp. 19S Rge. (E) 8 (W)

Location as "NE/CNW/SW4" or footage from lines C SW NE  
Lease Owner Pickrell Drilling Company  
Lease Name Blessing Well No. 1  
Office Address 705 Fourth National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 21, 1963  
Application for plugging filed September 21, 1963  
Application for plugging approved September 21, 1963  
Plugging commenced September 21, 1963  
Plugging completed September 21, 1963  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3434 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up with heavy mud to 215 feet. Followed by wooden plug and 1/4 sack hulls. Placed 21 sacks cement onto hulls. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss. John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
Box 332, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1963

My commission expires April 30, 1967  
Betty Brandt Notary Public.

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Pickrell Drilling Company  
705-4th National Bk. Bldg.  
Wichita, Kansas

DRILLING COMMENCED: August 28, 1963

CONTRACTOR: Graves Drilling Co., Inc.  
Box 332  
El Dorado, Kansas

DRILLING COMPLETED: September 2, 1963

CASING RECORD: 8 Jts. 226' - 8-5/8"  
surface casing with  
175 sacks cement

LOCATION: Blessing No. 1  
C SW NE  
Section 33-19S-8W  
Rice County, Kansas

-----

0 - 190	Shale & red bed
190 - 222	Shale
222 - 1105	Shale, clay & red bed
1105 - 1540	Shale & lime
1540 - 1825	Lime & shale
1825 - 2635	Shale & lime
2635 - 2746	Lime & shale
2746 - 2940	Lime
2940 - 3051	Shale & lime
3051 - 3240	Lime
3240 - 3357	Shale & lime
3357 - 3365	Sand & sandy shale
3365 - 3434	Lime, shale & sand
3434	Rotary Total Depth

RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *J. Graves*  
President

STATE OF KANSAS )  
                  ) SS  
BUTLER COUNTY )

Subscribed and sworn to before me, a Notary Public, this 6th day of September, 1963.

My commission expires:

April 30, 1967

*Betty Brandt*  
Betty Brandt Notary Public