

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellsworth County, Sec. 8 Twp. 15-S Rge. 7 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SE

Lease Owner Divanco Inc.

Lease Name Dolezal Well No. 1

Office Address P. O. Box 2002, Ponca City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-14 19 56

Application for plugging filed 9-14 19 56

Application for plugging approved 9-14 19 56

Plugging commenced 9-14 19 56

Plugging completed 9-14 19 56

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Grider of Wichita, Kansas office

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	pipe	8 5/8"	293'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300', set Halliburton Plug, 20 sacks of cement, filled hole to 25' with heavy mud, set Halliburton Plug, 55 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Springer & Harper

Address P. O. Box 187, Valley Center, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Harper

L. L. Harper P. O. Box 187, Valley Center, Kansas


SUBSCRIBED AND SWORN TO before me this 18th day of September, 1956

Seaward S. Grider
Notary Public.

My commission expires Jan. 31, 1957

RECEIVED
STATE CORPORATION COMMISSION
SEP 19 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 8 T 15 R 7W
BOOK PAGE 98 LINE 39



Locate well correctly on above Section Plat

SPRINGER & HARPER

DRILLING CONTRACTORS
VALLEY CENTER, KANSAS

September 17, 1956

Divanco Inc.,
P. O. Box 2002
Ponca City, Oklahoma

DOLEZAL NO. 1

SW/4 SW/4 SE/4
Section 8, Township 15-S,
Range 7-W,
Ellsworth County, Kansas

sand	0 - 20
clay & shells	80
lime & shale	160
gyp & shale	250
shale	284
lime	305
shale	410
lime	420
red-bed & shale	525
shale & shells	685
shale & salt	920
shale & anhydrite	995
anhydrite	1135
shale & anhydrite	1180
lime	1240
shale	1340
shells & shale	1410
shale	1460
lime & shale	1615
lime	1785
sandy lime	1805
lime & shale	2047
shale	2078
shale & lime	2285
shale	2325
lime	2417
lime & shale	2448
lime	2490
lime & shale	2587
shale	2628
sand & shale	2729
lime	T.D. 2940

CASING

Ran 293' of 8 5/8"
Surface Casing, cemented
with 225 sacks of cement.

TOPS

Heebner 2605
K.C. 2729

SPRINGER & HARPER

By L. L. Harper
L. L. Harper

RECEIVED
STATE OF KANSAS
29-19-56
GENERAL INVESTIGATION
DIVISION
WICHITA, KANSAS

PLUGGING
FILE SEC 8 T. 15 R. 7W
BOOK PAGE 98 LINE 39