


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-159-20080-0000
WELL PLUGGING RECORD

Rice County, Sec. 31 Twp. 19 Rge. 3 (E) 8 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines: SW SW SW
Lease Owner: Petroleum Management, Inc.
Lease Name: Habiger Well No. 1
Office Address: 1515 Wichita Plaza - Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed: November 13, 19 67
Application for plugging filed: November 13, 19 67
Application for plugging approved: November 14, 19 67
Plugging commenced: November 16, 19 67
Plugging completed: November 16, 19 67
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Gilbert Tolman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,426 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing			8 5/8"	208'	None
				4 1/2"	3,425'	2,918

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 3,365. Dumped 3 sacks cement. Mudded hole to 205'. Set rock bridge from 205' to 190'. Cemented to surface.

RECEIVED
DEC 4 1967
12-04-67
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Midway Drilling, Inc.
Address: Box 921 - Great Bend, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK ss.
H. G. Unruh (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
1515 Wichita Plaza - Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 1st day of December 19 67

MARIE C. MURPHY, Notary Public
My commission expires April 23, 1970

[Signature]
Notary Public.



NOTARIAL COMMISSIONER
 DEC 7 1967
 COMMISSION DIVISION
 WASHINGTON, MISSOURI

DRILLERS LOG

Habiger No. 1

CASING RECORD:	COMPANY:	Petroleum Management, Incorporated	DESCRIPTION:
8 5/8" @ 208'	CONTRACTOR:	Red Tiger Drilling Co.	SW SW SW of 31-19S-8W
w/185' ex cement	COMMENCED:	October 26, 1967	Rice County, Ks.
4 1/2" @ 3425'	COMPLETED:	November 3, 1967	
w/50' ex cement			
TOTAL DEPTH: 3426'			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Red Bed	0	75	
Red Bed, Shale & Sand clay	75	209	
Red Bed	209	244	
Anhydrite	244	264	
Shale	264	1070	
Shale (salt) w/Lime shells	1070	1360	
Lime & Shale	1360	2383	
Shale	2383	2430	
Lime	2430	2712	
Shale (Heebner)	2712	2716	
Douglas Shale	2716	2847	
Brown Lime	2847	2870	
Lime	2870	3185	
Conglomerate	3185	3250	
Conglomerate, Maquota	3250	3310	
Simpson, Lime & Shale	3310	3497	
Arbuckle	3497	3426	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 6th day of November, 1967.

Betty M. Maloney
 Betty M. Maloney
 Notary Public

My Commission Expires:
 3-22-71