

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-19271-0000

LEASE NAME Hill

WELL NUMBER 25-3

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 28 TWP. 19 RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 8-16-89

Plugging Completed 8-16-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE#(522-1560) OPERATORS LICENSE NO. 5822

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-16-89 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? w/cp-1

Producing Formation Kinderhook Depth to Top 3328 Bottom 3396 T.D. 3359

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	202	8 5/8	202	0
		0	3396	5 1/2	3396	1454'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed. from 1454' to 1150' and pumped sand back to 3280' spot 6 sacks of cement, pulled pipe at 1454' to 1150' and pumped 75' plug, pulled to 750' and pumped 75' plug, pulled to 380' pumped 4 hulls, pulled to 260' and pumped to surface with cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp License No. 5822

Address Box 322 Haysville Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Cop.

STATE OF Kansas COUNTY OF Sedgwick, ss. CONSERVATION DIVISION
Wichita, Kansas


K. Todd Allam (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) K. Todd Allam

(Address) Box 322 Haysville, Ks. 67060

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 89

My Commission Expires:



Gary D. Stearns
Notary Public

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

HILL #3
C NE SW SECTION 28-19S-8W
RICE COUNTY, KANSAS

COMMENCED: SEPTEMBER 27, 1963
COMPLETED: OCTOBER 5, 1963

OPERATOR - O. A. SUTTON

DEPTH	FORMATION	REMARKS
FROM TO		
0 204	SHALE & SAND	RAN 10 JOINTS 8-5/8" CASING, SET @ 202' W/ 190 SACKS CEMENT
204 900	CLAY, RED BED & SHALE	
900 1125	SHALE & SHELLS	
1125 1475	LIME	
1475 2430	SHALE & LIME	
2430 3245	LIME	
3245 3319	LIME & SHALE	
3319 3350	SAND & SHALE (CORE)	
3350 3403	LIME & SHALE	
3403 TD		RAN 3396' OF 5-1/2" CASING, SET @ 3396' W/ 75 SACKS CEMENT

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN THE C NE SW SECTION 28-19S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF OCTOBER, 1963, PERSON E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1967

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1969

CONSERVATION DIVISION
Wichita, Kansas