

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-19272-000

LEASE NAME Shepard

WELL NUMBER 26-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 28 TWP. 19 RGE. 8W (E) or (W)

COUNTY Rice

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE#(522-1560) OPERATORS LICENSE NO. 5822

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed _____

Plugging Commenced 11-27-89

Plugging Completed 11-27-89

The plugging proposal was approved on 11-27-89 (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? ? If not, is well log attached? N/A

Producing Formation kinderhook Depth to Top 3321 Bottom 3331 T.D. 3345

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	200	8 5/8	200	None
		0	3353	5 1/2	3353	2730

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand back to 3272 ft and spot 5 sacks cement, pulled pipe to 1150 ft and
spot 75 ft plug, pulled to 750 ft and spot 75 ft plug, pulled to 260 ft
and circulated cement to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Copr. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.


K. Todd Allam (Employee of Operator) of Wichita (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) K. Todd Allam

(Address) Haysville, Ks. 67060

SUBSCRIBED AND SWORN TO before me this 13 day of December, 19 89

My Commission Expires _____



Notary Public

GABBERT-JONES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

SHEPHERD #1
C SE SW SECTION 28-19S-8W
RICE COUNTY, KANSAS

COMMENCED: DECEMBER 2, 1963
COMPLETED: DECEMBER 10, 1963

OPERATOR - O. A. SUTTON

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	200	SURFACE SAND	RAN 9 JOINTS 8-5/8" CASING, SET @ 200' W/ 190 SACKS CEMENT.
200	650	RED BED & SHALE	
650	1260	SHALE & SHELLS	
1260	1555	LIME & SHALE	
1555	1790	LIME	
1790	2475	LIME & SHALE	
2475	2768	LIME	
2768	2900	SHALE & LIME	
2900	3215	LIME	
3215	3318	LIME & SHALE	
3318	3353	CORE	
3354	TD		RAN 103 JOINTS 5-1/2" CASING, SET @ 3353' W/ 75 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL
DRILLED IN C SE SW SECTION 28-19S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE
AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE,
ON THIS 11TH DAY OF DECEMBER, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY
KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND
ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED
FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY
AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1967

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

RECEIVED
STATE CORPORATION COMMISSION

AUG 22 1989

CONSERVATION DIVISION
Wichita, Kansas