

15-159-30175-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 28 Twp. 19 Rge. 8W (XX) (W)

Location as "NE/CNWSW" or footage from lines C SW SE
Lease Owner Kewanee Oil Company
Lease Name West Lyons Unit #27 Well No. 1
Office Address Box 360, Hoisington, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 8-24 19 65
Application for plugging filed 1-12 19 72
Application for plugging approved 1-13 19 72
Plugging commenced 2-17 19 72
Plugging completed 2 -21 19 72
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 2-16 1972
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Kinderhook Depth to top 3345 Bottom _____ Total Depth of Well 3412 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2"	3411'	2623.43'
				8-5/8"	212'	


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 3330', mixed and ran 5 sacks cement through dump bailer.
Mudded hole to 235', set 15' rock bridge. Filled hole with 3-1/2 yards ready-mix from 220' to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Southwest Casing Pulling Company
Address Box 364, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Billie Oden (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
C. W. Mosier
(Signature)



Box 2093, Wichita, Kansas 67201
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of March, 19 72

My commission expires 8-10-75
Billie Oden Notary Public.

GEOLOGICAL REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1972
CONSERVATION DIVISION
Wichita, Kansas

O. A. SUTTON #1 Goodfellow
app. C SW SE Section 28-19S-8W
Rice County, Kansas

ELEVATION: 1717' (All measurements are from Kelly bushing)

COMMENCED: August 18, 1965

SURFACE CASING: 8 5/8" casing set at 212' with 190 sacks GL-3.

UNDER SURFACE: August 19, 1965

COMPLETED: 5 1/2" casing set at 3411' with 100 sacks on August 24, 1965

FORMATION TOPS:

Log tops:	Heebner	2727 (-1010)
	Brown lime	2863 (-1146)
	Lansing	2897 (-1180)
	Base Kansas City	3209 (-1492)
	Base Lithographic lime	3276 (-1559)
	Kinderhook sand	3345 (-1628)
	Base sand	
	Maquoketa	3381 (-1664)
	Rotary Total Depth	3412 (-1695)

ZONES OF POROSITY AND STAINING:

Kinderhook sand Section

First Sand 3292-1575

This sand was clear to frosted, subangular to subrounded, medium grain size, good porosity. No show.

Second Sand 3345-1628

- Core #1 Lost bottom 5' of core, total amount of sand recovered 17'.
- 3337-3367 Cored 30', recovered 25'.
- 3337-3344.3 Shale, gray to gray-green, waxy in part, platy.
- 3344.3-3345.4 Shale as above with abundant sand lenses.

Purchased well, do not have driller's log.