

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-19274-0000

LEASE NAME Keile

WELL NUMBER 14-1

660 Ft. from S Section Line
4620 Ft. from E Section Line

SEC. 21 TWP. 19 RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed 1-3-64

Plugging Commenced 7-28-89

Plugging Completed 7-28-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE#() 522-1560 OPERATORS LICENSE NO. 5822

Character of Well input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-28-89 (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? W/CP-1

Producing Formation kinderhook Depth to Top 3320 Bottom 3330 T.D. 3350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content surface	From	To	Size	Put in	Pulled out
		0	206	8 5/8	206	None
	Kinderhook	0	3386	5 1/2	3386	2550

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand back to 3270 ft, spot 6 sacks cement, pull pipe, pull to 1150 ft and
pump 35 sacks cement, pulled to 750 ft and pump 35 sacks cement, pulled and
bumped cement from 260 ft to surface, recemented surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.


(Signature) K. Todd Allam

(Address) Box 322 Haysville, Ks. 67060

Subscribed and sworn to before me this 31 day of August, 19 89

Gary D. Stearns
Notary Public

My Commission Expires:



WICHITA, KANSAS
DRILLERS WELL LOG


#1 KLEILE
C SW SW SECTION 21-19S-8W
RICE COUNTY, KANSAS

COMMENCED: JULY 1, 1963
COMPLETED: JULY 9, 1963

OPERATOR - O. A. SUTTON

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	206	CLAY & SAND	RAN 10 JOINTS 8-5/8 INCH CASING, SET @ 206' W/ 185 BAGS CEMENT
206	1150	SHALE	
1150	1600	LIME & SHALE	
1600	1950	LIME	
1950	2225	SHALE W/ LIME	
2225	2455	SHALE & SHELLS	
2455	2600	SHALE & SAND	
2600	2670	LIME & SHALE	
2670	2730	LIME	
2730	2880	LIME & SHALE	
2880	2970	LIME & SHALE STREAK	
2970	3260	LIME	
3260	3285	LIME & SHALE	
3285	3338	CORING	
3338	3389	LIME	
3389	TD		RAN 104 JOINTS 5-1/2" CASING, SET @ 3389' W/ 75 BAGS CEMENT

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE WELL DRILLED IN C SW SW SECTION 21-19S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.


E. E. HALL

STATE OF KANSAS }
 } SS
COUNTY OF SEDGWICK }

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 11TH DAY OF JULY, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.


VERA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963