

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-19276-0000

LEASE NAME Bohnke

WELL NUMBER 8-1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 21 TWP. 19S RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed 10-3-63

Plugging Commenced 8-2-89

Plugging Completed 8-2-89

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gressel Corp.

ADDRESS Box 322 Haysville, Ks. 67060

PHONE#(522-1560) OPERATORS LICENSE NO. 5822

Character of Well input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-2-89 (date)

by Jack Luthie (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? w/CP-1

Producing Formation Kinderhook Depth to Top 3309 Bottom 3334 T.D. 3345

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	surface	0	202	8 5/8	202	None
	Kinderhook	0	3309	5 1/2	3309	1603

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sand back to 3250 ft, spotted 6 sacks cement, pulled pipe, pumped 35 sacks cement and water at 1150 ft. Ran tubing to tag plug at 725', pulled tubing to 270 ft pumped cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) K Todd Allam

(Address) Box 322 Haysville, Ks. 67060

RECEIVED


STATE CORPORATION COMMISSION

AUG 31 1989

SUBSCRIBED AND SWORN TO before me this 31 day of August, 1989

CONSERVATION DIVISION

Wichita, Kansas Commission Expires:



Notary Public

DRILLER'S LOGJULY 23, 1963

#1 Behnke, C NW NW
Section 21-19S-8W
Rice County, Kansas


Date Commenced - July 12, 1963

Date Completed - July 19, 1963

OPERATOR: O. A. Sutton

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
From	To		
0	60	Soil	
60	202	Shale/Lime	
202	725	Shells/red bed/Lime	Ran 10 Jts. 8-5/8"
725	1130	Red Bed/Shale	used casing to 202',
1130	1245	Shale/Lime	Cem with 185 sx HA5.
1245	1470	Shale/Lime	
1470	1545	Lime	
1545	1695	Lime	
1695	1950	Lime	
1950	2215	Lime	
2215	2365	Lime	
2365	2529	Lime	
2529	2665	Lime	
2665	2750	Lime	
2750	2885	Lime	
2885	2960	Lime	
2960	3035	Lime	
3035	3109	Lime	
3109	3170	Lime	
3170	3238	Lime	
3238	3300	Lime	
3300	3302	Core #1	
3302	3334	Core #1	
3300	3334	Reaming Core Hole	
3334	3391	Lime/Shale	
3391		Total Depth (T.D)	Ran 104 Jts. 5-1/2" Csg. Cem 1' off bottom with 75 sx salt satt. Common Cem.

I, JAMES S. SUTTON, certify that to the best of my knowledge and belief, this is a true and correct copy of the Driller's Log for the well drilled in the Center of the NW NW Section 21-19S-8W, Rice County, Kansas.


James S. Sutton

STATE OF KANSAS)
) ss
SEDGWICK COUNTY)

Beofre me, the undersigned, a Notary Public, within and fore said county and state, on this 23rd day of July, 1963, personally appeared JAMES S. SUTTON, to me personally known to be the identical person who exeucted the within and foregoing instrument