

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20286-00-01
Spot: SESESW Sec/Twnshp/Rge: 10-17S-40W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: CLAYPOOL Well Number: 1-10
County: GREELEY Total Vertical Depth: 3040 feet

Operator License No.: 8076
Op Name: GAMMA RESOURCES, INC.
Address: PO BOX 800
LIBERAL, KS 67905

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 282 WITH 185 SX CMT
Production: Size 4.5 feet: 3030 WITH 600 SX CMT
Liner: Size _____ feet: 98.80

Well Type: SWD UIC Docket No: D24590.0 Date/Time to Plug: 12/14/2000 10:40 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: ROB WILLIAMS Company: GAMMA RESOURCES Phone: (316) 624-6405

Proposed Plugging Method: FILL 4 1/2" CASING WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/14/2000 11:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 1760-1900'. PUMPED DOWN 4 1/2" CASING 100# HULLS AHEAD WITH 200# HULLS MIXED IN FIRST PART OF CMT. PUMP 165 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 400#. 4 1/2" X 8 5/8" ANNULUS HAD CMT AT SURFACE.

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

JAN 02 2001

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED

DATE 1/3/01

DEC 22 2000

INV. NO. 2001061223

MP

Form CP-208