

5 030480

3-9

8000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 115-21,176 (Drld 1985)
C NE, SEC. 32, T. 19 S, R 5 ~~WE~~
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7796
Operator: Bond Oil
Name & Address Box 151
Marion, KS 66861

Lease Name Higgins Well # 2
County Marion 76.38
Well Total Depth 2350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8-5/8" feet 219' / 150 sx

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Flowers Well Service License Number 7120
Address Peabody KS

Company to plug at: Hour: 12:00p Day: 9 Month: 3 Year: 19 89

Plugging proposal received from Rex Savage
(company name) Bond Oil (phone) 316-382-3438

were: 4-1/2" @ 2350' w/420 sx - 8-5/8" @ 200' - perfs 224'-96' - sand 2190' -
cap w/4 sx - recover available pipe - circ cement 250

Plugging Proposal Received by Johnny Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 18:00 Day: 9 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT Sanded to 2185' - capped w/4 sx cement by bailer. Ran bond
log cement @ approx 680' - shot pipe off @ 644' - pulled out of hole to 247' - circ
cement to surface using 90 sx slurry cement. Pump broke down - bailed hole to
cement - filled hole to surface. Builders Concrete #25252

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-17-89
WV. NO. 24130

WC

Signed Merlan Unruh
(TECHNICIAN)

*Rec'd 3-16-89
KCC*