

1041400

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-21,900-0000
C NE NW SEC. 35, T 30 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WARREN WELL # 2-35

TECHNICIAN'S PLUGGING REPORT 6/15 COUNTY BARBER 159.25

OPERATOR LICENSE # 5030 WELL TOTAL DEPTH 4900 FEET

OPERATOR: VESS OIL CORPORATION PRODUCTION CSG: SIZE 7" @ 4765' WITH 300 SX

NAME AND 8100 E 22ND ST N, BLDG. 300 SURFACE CASING: SIZE 13 5/8" @ 287' WITH 300 SX

ADDRESS WICHITA, KS 67226 CONDUCTOR CSG: SIZE 20" @ 20'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-23,997 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

RECEIVED

STATE CORPORATION COMMISSION

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 15 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

JUN 30 2000
6-30-00

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945 CONSERVATION DIVISION
Wichita, Kansas

WERE: PERFS AT 4264-70. OPEN HOLE AT 4765-4900 JUNK IN HOLE PART OF DISPOSAL & PRODUCTION
STRING IN HOLE. ALSO BAKER MODEL-O PACKER AT 4390'. TOP OF TUBING STRINGS APP. 3330 & 2820

SET CIBP AT 2820' AND PUT 2 SX CEMENT ON TOP OF CIBP. SPOT PLUGS THROUGH 7" CASING. RUN

GEL SPACER BETWEEN PLUGS. 1ST PLUG AT 727' WITH 75 SX CEMENT. 2ND PLUG AT 300' WITH 75

SX CEMENT. 3RD PLUG AT 40' WITH 40 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:00 AM DAY: 15 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT

SET CIBP AT 2820' AND PUT 2 SX CEMENT ON TOP OF CIBP. SPOT PLUGS THROUGH 7" CASING. RUN

GEL SPACER BETWEEN PLUGS. 1ST PLUG AT 727' WITH 75 SX CEMENT. 2ND PLUG AT 300' WITH 75

SX CEMENT. 3RD PLUG AT 40' WITH 40 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1600' OF 7" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID)OBSERVE THIS PLUGGING

INVOICED

SIGNED

Stephen J. Pfeifer SA
(TECHNICIAN)

DATE 7/5/00

FORM CP-2/3

WV. NO. 1060017

(Handwritten signature/initials)