

15-007-30208-0000

6-24-88

347

1 040132

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 6/5/68  
C NW NW, SEC. 34, T 30 S, R 12 W Ex  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087  
Operator: Texas Energies, Inc.  
Name & Address: P.O. Box 947  
Pratt, KS 67124

Lease Name Spicer Well # 1  
County Barber 117.72  
Well Total Depth 3662 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 323

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:15 a.m. Day: 24 Month: 6 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 5 1/2" at 3662' PBD 3594' Perfs at 3577-87'

1st plug sand back to 3461' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 24 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3461' and dumped 5 sx cement on top  
of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1500' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

JUL 5 1988  
7-3-88

INVOICED

DATE 7-19-88

INV. NO. 21446

observe this plugging.

Signed Stephen J. Pfeifer  
(TECHNICIAN)