

1 121082

11-9

Docket #

API NUMBER 15- E-26,108 15-007-20114-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

C S/2, SEC. 34, T 30 S, R 12 W/E
1320 feet from S section line
2640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435
Operator: Bowers Drilling Company, Inc.
Name & Address: 125 N. Market, Ste. 1425
WICHITA, KS 67202

Lease Name Haas Well # 1
County Barber 121.03
Well Total Depth 3724 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 203

Abandoned Oil Well _____ Gas Well _____ Input Well SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 11 a.m. Day: 9 Month: 11 Year: 1995

Plugging proposal received from Bill Musgrove

(company name) Bowers Drilling Co., Inc. (phone) 316-886-5520

were: 4 1/2" at 3724' w/100 sx cement, PBTD 3676', Perfs at 3560-64, 3643-51'

1st plug pump 1 sx hulls and 30 sx common cement. Stop plug at 3200' at 1200#.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20 p.m. Day: 9 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug squeezed 4 1/2" perfs with 30 sx cement. Shut in pressure 1200#.

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Pumping pressure 0-800 psi and shut in 600 psi.

4 1/2" collar welded in 8 5/8" surface casing.

RECEIVED STATE CORPORATION COMMISSION NOV 16 1995 WICHITA, KANSAS

Remarks: Used 65/35 Pozmix 6% gel by Allied. Recovered 2365' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (do not check) observe this plugging.

DATE 11-20-95

Signed [Signature] (TECHNICIAN)

INV. NO. 44054 11-9