

To: 1 040131
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-24-88 346
API NUMBER 15- 007-20,563-000
NE SW NE, SEC. 33, T 30 S, R 12 W 5E
3630 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Operator: Texas Energies, Inc.
Name & Address: P.O. Box 947
Pratt, KS 67124

Lease Name Olson Well # 1
County Barber 149.63
Well Total Depth 4604 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:30 p.m. Day: 24 Month: 6 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 4580' PBD 4222' Perfs at 3683.5-3685.5, 4393-4396, Plug at 4220-22'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 750 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2900' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.) Kansas

INVOICED
Observe this plugging.

DATE 7-19-88

INV. NO. 21445

Signed Stephen J. Pfeifer (TECHNICIAN)