

1 010269

7-22-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-20,620-0000

S/2 SW NE, SEC. 32, T 30 S, R 12 W/E
2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Olson Well # 1

Operator: Raymond Oil Company, Inc.
Name & Address: P.O. Box 48788
Wichita, KS 67201

County Barber 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:05 a.m. Day: 22 Month: 7 Year: 19 87

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling (phone) 316-948-2457

were: 4 1/2" at 3820' Perfs at 2940-47' Elevation 1793' GL

1st plug sand back to 2890' and dump 4 sx cement on top of sand through bailer,

2nd plug run tubing to 600' and pump 40 sx cement,

3rd plug pump 40 sx cement at 310',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow & Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 22 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 2890' and dumped 4 sx cement on top of sand through bailer,

2nd plug ran tubing to 617' and pumped 50 sx cement,

3rd plug pulled 10 joints to 311' and pumped 50 sx cement,

4th plug pulled tubing to 40', pumped 10 sx cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
7-24-87
JUL 24 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2489' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-24-87

Signed [Signature] (TECHNICIAN)

INV. NO. 17622

7-22

Petru-Log

Radiation Guard Log

COMPANY RAYMOND OIL COMPANY

WELL OLSEN #1

FIELD _____

COUNTY BARBER **STATE** KANSAS

Location S/2-SW-NE

Other Services:
CDL

Sec. 32 **Twsp.** 30S **Rge.** 12W

Permanent Datum: GROUND LEVEL **Elev.** 1793

Elev.: K.B. 1806

Log Measured From K.B., 13 Ft. Above Perm. Datum

D.F. 1803

Drilling Measured From KELLY BUSHING

G.L. 1793

Date	6/8/78						
Run No.	ONE						
Depth—Driller	3900						
Depth—Logger	3893						
Btm. Log Inter.	3892						
Top Log Inter.	SURF.						
Casing—Driller	8 5/8	•	279	•	•	•	•
Casing—Logger							
Bit Size	7 7/8						
Type Fluid in Hole	STARCH						
Dens.	Visc.	9.9	49				
pH	Fluid Loss	7.5	8.8 ml	ml	ml	ml	ml
Source of Sample	FLOWLINE						
R₁₀₀ @ Meas. Temp.	.1	•	80 °F	•	•	•	•
R₁₀₀ @ Meas. Temp.	.07	•	80 °F	•	•	•	•
R₁₀₀ @ Meas. Temp.	.14	•	80 °F	•	•	•	•
Source: R₁₀₀ R₁₀₀	CHARTS						
R₁₀₀ @ BHT	.07	•	115 °F	•	•	•	•
Time Since Circ.	2 HRS.						
Max. Rec. Temp.	115 °F			°F	°F	°F	°F
Equip. Location	H-5		GB				
Recorded By	DAN THOMPSON						
Witnessed By	MR. DICK ROWLAND						

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1987

5-19-87

CONSERVATION DIVISION
Wichita, Kansas