

5030210

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-115-21,122 0050

C/SE/SE, SEC. 14, T. 18 S. R. 4 NE

330 feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9730

Lease Name COTT Well # B-1

Operator Name: The Merlin Corporation

County Marion 38.35

Address 509 Union Center
Wichita, Ks 67202

Well Total Depth 1180 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 7 feet 200

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allied Conty License Number _____

Address Russell, Ks

Company to plug at: Hour: 9³⁰ Am Day: 3 Month: May Year: 19 86

Plugging proposal received from Lloyd Davis

(company name) Consultant - Merlin Corp. (phone) 913/483-3246

were: 4 1/2" @ 1177' - Perfor 1150'-54' - No pipe recovery!

Fill Pipe w/ cement; pump plug to 150', to
save well casing for water well for farmer. Pump
Cement in 7" - 4 1/2" Annulus 150' to 250' from surface

Plugging Proposal Received by Merlan Urrub
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11¹⁵ Am Day: 3 Month: May Year: 19 86

ACTUAL PLUGGING REPORT Injection Rate 3 1/2 BBLs/min @ 300⁺ Psi, mixed
+ pumped in hole 2 hulls w/ approx 50 sac Cement, followed by
plug with complete shut off @ 2000⁺ Psi - plug @ 40', by
measuring line. mixed + pumped approx 50 sac cement
1/2 of hulls down 4 1/2" - 7" annulus w/ shut off @ 800⁺ Psi.

Remarks: Allied Conty # 182 used 60/40 Poz 49 gal
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~

observe this plugging. STATE CORPORATION COMMISSION

Signed Merlan Urrub
(TECHNICIAN)

DATE 5-23-86

MAY 23 1986 05-23-86

INV. NO. 13947

JUL 02 1986 WICHITA, KANSAS AUG 7 1986

