

6-24-88 15-007-21437-0000 349

API NUMBER 15-Docket #D-21,933

To: 1 040133  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SE SE, SEC. 28, T 30 S, R 12 W/EX  
330 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Lilliequist Well # 1-28

Operator: Texas Energies, Inc.

County Barber 152.43

Name & Address P.O. Box 947

Well Total Depth 4690 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:30 a.m. Day: 24 Month: 6 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 5 1/2" at 4570' Perfs at 4034-35, 4163-64, Open hole at 4570-4690'

1st plug set CIBP at 4020' and dumped 2 sx cement on top,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:15 a.m. Day: 24 Month: 6 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4020' and dumped 2 sx cement on top of plug with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 650 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3158' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 7-19-88

INV. NO. 21448